


SHOP FLOOR - 1:100



SURVEY OVERLAID



Description of Amends 20.02.2024/9681 - Witney- P1F19/0D Non Food Exit 1. Ambient end removed from 4 gondolas (4 bays total) 2. Side racks and plinths relocated to suit		Wall finishes Always refer to latest building specification spreadsheet on portal for technical specifications for the required top coat & undercoat paints and cladding materials. For refit stores perimeter walls that are not scoped to receive freeze board, and perimeter mdf clad wall columns are to be painted floor to ceiling in Dulux Satin Ivory 4 by default unless marked as another colour on the CAD. Areas to be painted alternative colours either Imperial Ivy 5 (Gen2) or Lime zest (Gen1/Evo) will be clearly marked on this CAD drawing. Stores that are scoped to receive freeze board should be painted floor to underside of freeze (approx 2.1m h). Areas behind BWS and around kiosks and walls with no equipment (e.g. behind checkouts above windows) in general will need to be decorated floor to ceiling as no freeze will be scoped in these areas. All low speed rebrand stores, existing peristop clad wall columns and walls may be overlaid with non PVC cladding material by the internal graphics contractor in the required colour (Imperial Ivy/Gen2/Lime zest/Gen1/Evo) or Ivory. Existing peristop finishes should not be painted. ATM housing should be decorated where possible to match the colour of the main elevation they are adjacent to. The mdf & paint specification for refit stores should also apply to rebrand stores. Stand alone column finish - All formats Refer to latest building specification spreadsheet on portal for technical specifications. All stand alone peristop finish columns in the body of the store to be clad in PVC free cladding material by the internal graphics contractor unless stated otherwise. Columns to be edged with 38mm grey edge trim and grey bump rails as per the agreed specification. All columns must be finished in peristop before applying the cladding material to ensure the cladding material adheres. MDF is not a suitable material to apply cladding material to. All column cladding colours will be marked on the CAD by graphics contractor (either Imperial Ivy, Lime zest or Ivory depending on location) except for circular columns which if not boxed out must be decorated saddle ivory All columns must be finished in peristop before applying the cladding material to ensure the cladding material adheres. MDF is not a suitable material to apply cladding material to. All column cladding colours will be marked on the CAD by graphics contractor (either Imperial Ivy, Lime zest or Ivory depending on location) except for circular columns which if not boxed out must be decorated saddle ivory		Standard Notes Please refer to the Asset Planning Standard Notes for applicable information. All dimensions to be checked on site and any discrepancy to be verified with the co-operative group or its agents before proceeding with the work. This prime purpose of this plan is for retail sales floorshop fitting. For further detail regarding this project refer to red book or drawing portal. Licensing Application Process Statement: 'We will comply with our statutory requirements' All box outs to be to the ceiling unless otherwise stated. Existing ceiling plans for refits are available on request. Management of Asbestos As part of our compliance with the Management of Asbestos Regulations, service providers must comply with the Co-operative Group's Management of Asbestos Containing Materials policy and processes. Service providers are to access the Co-operative Group's web-based asbestos register, www.365online.co.uk prior to undertaking any works. Any difficulty in obtaining asbestos information must be brought to our immediate attention and is not an excuse for working without this.		CDM Regulations 2015 The designers at the Co-operative wish to point out that the CDM Regulations 2015 apply to this work and the project may require notification to the HSE. Under their duty imposed by the CDM Regulations 2015 the designers have attempted to eliminate hazards so far as is reasonably practicable during design and where hazards could not be avoided the designers have reduced the risks associated. The remaining hazards and foreseeable risks that could not be designed out of the project have been identified as below: FALLS: from heights during installation of suspended ceilings; taking deliveries over raised loading bays; as a result of split level floors and steps HAZARDOUS MATERIALS: i.e. asbestos - to be removed as necessary by specialist, see the Co-operative Group's Management of Asbestos Containing Materials policy and processes. EQUIPMENT: ensure there are controls and training in place regarding the use and suitability of all equipment on site. MANUAL HANDLING: shelving, metal studs, boards etc PROTECTION: site operatives and Co-operative Group employees are to be protected at all times. Some of the work is to be undertaken out of hours. Work areas are not to be used by Co-operative Group staff during the alterations. The CDM coordinator is to be consulted with regard to the phasing of any work. SERVICES: buried services may exist under the floors and behind panels, with their exact position unknown. The contractor is to ascertain the location of all services prior to the commencement of works on site. PETROL STATIONS - RISK OF EXPLOSION OF PETROL FUMES: please refer to The Guidance For The Design, Construction, Modification and Maintenance Of Petrol Filling Stations ('The Blue Book') before undertaking any work. ADDITIONAL DESIGNERS NOTES: any significant or unusual risks are highlighted in the drawing.		Exceptions Any areas of the proposal that are not in-line with the current model should be detailed here along with the reason and thinking behind it. To also include any by-laws or covenants. Store Demographic: Striving: No Checklist Added: Asset Planner: Date: Risk Rating: Planning: Lease:		Additional Equipment VND Magazines Cards Impulse Confect. Impulse CSN Pizza Step ISB BWS Prom Eden Bakery Stand Grocery Prom Electrical Shelving Roll Cages BOH Promo Plinths		Drawing Information <table border="1"> <tr> <th></th> <th>Existing</th> <th>Proposed</th> </tr> <tr> <td>Gross Building Area (GBA)</td> <td>Sq.Ft.</td> <td>Sq.Ft.</td> </tr> <tr> <td>Gross Sales Area (GSA)</td> <td>13,108 Sq.Ft.</td> <td>Sq.Ft.</td> </tr> <tr> <td>Net Sales Area (NSA)</td> <td>13,026 Sq.Ft.</td> <td>Sq.Ft.</td> </tr> </table> Back of House Information <table border="1"> <tr> <th></th> <th>Sq.Ft.</th> <th>Sq.Ft.</th> </tr> <tr> <td>Back Of House</td> <td>8,496 Sq.Ft.</td> <td>Sq.Ft.</td> </tr> <tr> <td>Back Up Chilled</td> <td>Sq.Ft.</td> <td>Sq.Ft.</td> </tr> <tr> <td>Back Up Frozen</td> <td>Sq.Ft.</td> <td>Sq.Ft.</td> </tr> </table> Drawn By: SS Email: @coop.co.uk Scale: 1:100 Meetings <table border="1"> <tr> <td>Drawing Review</td> <td>xx/xx/xxxx</td> </tr> <tr> <td>Sign Off Meeting</td> <td>xx/xx/xxxx</td> </tr> </table> Drawing Status Stage 5: Locked CAD			Existing	Proposed	Gross Building Area (GBA)	Sq.Ft.	Sq.Ft.	Gross Sales Area (GSA)	13,108 Sq.Ft.	Sq.Ft.	Net Sales Area (NSA)	13,026 Sq.Ft.	Sq.Ft.		Sq.Ft.	Sq.Ft.	Back Of House	8,496 Sq.Ft.	Sq.Ft.	Back Up Chilled	Sq.Ft.	Sq.Ft.	Back Up Frozen	Sq.Ft.	Sq.Ft.	Drawing Review	xx/xx/xxxx	Sign Off Meeting	xx/xx/xxxx	WITNEY 11, HIGH STREET WITNEY OXFORDSHIRE OX28 6HW Store Phone No: 01993 703579 Format: MMP Hub Number: 9681 Drawing Information Brief Description Of Works: Proposed Fixture Layout Latest system drawing Job Originated By: Refurbishment/Acquisition Programme 2017 Drawing No: WITNEY-P2 Fixture Rev: F19 Macro Rev: M19 The Co-Op 1 Angel Square, Manchester, M80 9AG Only scales on A1	
	Existing	Proposed																																									
Gross Building Area (GBA)	Sq.Ft.	Sq.Ft.																																									
Gross Sales Area (GSA)	13,108 Sq.Ft.	Sq.Ft.																																									
Net Sales Area (NSA)	13,026 Sq.Ft.	Sq.Ft.																																									
	Sq.Ft.	Sq.Ft.																																									
Back Of House	8,496 Sq.Ft.	Sq.Ft.																																									
Back Up Chilled	Sq.Ft.	Sq.Ft.																																									
Back Up Frozen	Sq.Ft.	Sq.Ft.																																									
Drawing Review	xx/xx/xxxx																																										
Sign Off Meeting	xx/xx/xxxx																																										