

### **Works required Corn Exchange Penetrating damp.**

The current block paver and slab roadway inclines into the side elevation of the corn Exchange above DMP level causing a penetrating damp issue within the building.

Intended works to correct this issue are to lift a section of block pavers and install a ACO drainage channel connected to an existing storm water drain, and relay block pavers into drainage channel.

Required works

Fence off area of work.

Lift relevant area of block pavers and set aside for reuse.

Install 20m ACO drainage channel with fall leading into existing storm water drain.

Reinstall block pavers into new ACO drainage channel.

Clean and clear site upon completion of works.