

### Corn Exchange Drainage Works Langdale Gate

Contractor 1 Work	Cost	Contractor 2 Work	Cost
CAT scan site, excavate to side of Corn Exchange 8m x 1.2m x 400mm dispose of arisings, supply lay DPM, supply lay 50mm perforated pipe and connect to existing storm water drain, supply lay 300mm deep 4-20mm stone, supply lay geotextile layer, supply and lay Piora Paving an 50mm porous bed. Quote dose not allow to move services if required.	£8,168.70	Temporary fence, lift and set aside existing block paving, supply and install 20m run ACO channel connected to existing storm water drain, re-lay block paving clean and clear site.	£3,473.00
Welfare using WTC facilities		Welfare using WTC facilities	