



1, Front corner to Vicarage gate

Vicarage gate

2- gate to gate

Glebe gate

3- from gate to The Leys

- Area 1;
- 2 Trees to be removed & stumps ground
 - 10sqm wall to rebuild
 - 65sqm to repoint
 - 35m of coping to remove, remove vegetation & re-bed
- Area 2;
- 1 tree to remove & stump grind
 - 13sqm wall to rebuild
 - 8sqm wall to repoint
- Provisional sum to remove additional root & rebuild wall & fence to vicarage/school area
- Area 3;
- 40sqm wall to take down & rebuild
 - Propping required
 - 26sqm wall to repoint
- Allowance for new stone if required- provisional sum